

TIE-IN #1 @ APTOS BEACH DR. & TREASURE ISLAND AVE.
 INSTALL:
 1-8-INCH X 6-INCH TEE, FLG.
 2-8-INCH G.V., FLG. X M.J.
 1-6-INCH G.V., FLG. X M.J.
 2-6-INCH TRANSITION COUPLING
 1-CHLORINE TAP PER SCWD S-23.

APPLY 3,900 S.F. OF TYPE II SLURRY SEAL
 (ENTIRE ROADWAY-EDGE TO EDGE)

CONTRACTOR SHALL INSTALL
 APPROPRIATE FITTINGS TO
 AVOID CONFLICT WITH EXISTING
 STORM DRAIN.

TIE-IN #2 @ APTOS BEACH DR. &
 TREASURE ISLAND AVE.
 INSTALL:
 1-6-INCH CROSS, FLG.
 2-6-INCH G.V., FLG. X M.J.
 2-6-INCH G.V., FLG.
 2-6-INCH X 4-INCH FLG. REDUCER
 2-4-INCH FLG. X M.J. ADAPTER
 2-4-INCH TRANSITION COUPLING
 CONTRACTOR TO INSTALL 6-INCH CROSS
 WITH APPROPRIATE FITTINGS TO ADJUST
 FOR VARYING ELEVATION CHANGE
 BETWEEN EXISTING 4-INCH MAIN AND
 NEW 6-INCH MAIN AND TO AVOID
 CONFLICT WITH EXISTING STORM DRAIN.

INSTALL JONES J-3740
 6-INCH STEAMER FIRE
 HYDRANT PER SCWD STD.
 PLANS S-9 & S-10.
 EXACT LOCATION TO BE
 DETERMINED IN FIELD BY
 DISTRICT INSPECTOR.

RELOCATE SERVICE TO
 EDGE OF ROADWAY AND
 RECONNECT CUSTOMER
 SIDE PLUMBING (TYP.)

RELOCATE SERVICE JUST
 OUTSIDE OF FENCE AND
 RECONNECT CUSTOMER
 SIDE PLUMBING (TYP.)

THIS PROPERTY IS
 SERVED FROM THE
 FRONT ON APTOS
 BEACH DRIVE.
 (NO CHANGE IN
 WATER SERVICE)

RELOCATE SERVICE
 AND RECONNECT
 CUSTOMER SIDE
 PLUMBING (TYP.)

THESE PROPERTIES
 SERVED FROM THE
 FRONT ON TREASURE
 ISLAND AVE.
 (NO CHANGE IN
 WATER SERVICE)

THIS PROPERTY IS
 SERVED FROM THE
 FRONT ON TREASURE
 ISLAND AVE.
 (NO CHANGE IN
 WATER SERVICE)

INSTALL 2 SEPARATE
 DOMESTIC SERVICES
 PER SCWD STD.
 PLAN S-3. SAWCUT
 AND PATCH EXISTING
 CONCRETE DRIVEWAY

RELOCATE SERVICE
 AND RECONNECT
 CUSTOMER SIDE
 PLUMBING

INSTALL 2-INCH
 PERMANENT BLOW
 OFF PER SCWD STD.
 PLAN S-12.

RECONNECT EXISTING
 2-INCH FIRE AND
 DOMESTIC COMBINATION
 SERVICE.

RECONNECT EXISTING
 2-INCH FIRE AND
 DOMESTIC COMBINATION
 SERVICE.

RELOCATE SERVICE TO
 EDGE OF ROADWAY AND
 RECONNECT CUSTOMER
 SIDE PLUMBING (TYP.)
 SAWCUT CONCRETE AND
 REPLACE VOID WITH
 CONCRETE.

ABANDON EXISTING VALVES
 AND 2-INCH STL MAIN.

INSTALL:
 1-6-INCH FLG. TEE
 3-6-INCH G.V., FLG. X M.J.

INSTALL 2-INCH
 PERMANENT BLOW
 OFF PER SCWD STD.
 PLAN S-12.

ABANDON EXISTING
 2-INCH STL MAIN.

INSTALL 6-INCH IN
 LINE VALVE PER
 SCWD STD. PLAN
 S-6.


ALL JOINTS UP
 HILL SHALL BE
 RESTRAINED

NOTE 1.
 TURN OFF EXISTING SERVICE AT
 ANGLE METER STOP (OR CUT
 AND PLUG) TO REMOVE SERVICE
 AND CONCRETE FROM PROPOSED
 TRENCHLINE.
 SCWD WILL TEMPORARILY FEED
 345 THROUGH A HOSE-TO-HOSE
 FROM 308.
 INSTALL NEW SERVICE TO 345.

TREASURE ISLAND AVE.
 MAIN REPLACEMENT

SOQUEL CREEK
 WATER DISTRICT
 PO Box 158 Soquel, California 95073
 Phone Number: (831) 475-8500
 Fax Number: (831) 475-4291

CW. NO. 03-117
 DATE: 01/07/02
 SCALE: 1"=20'
 DESIGN BY: TAD
 DWG. NO. D-03-2115-P



Jeffery N. Gailey
 Chief Engineer
 Engineering Manager

SHEET:
 D-6

No.	Revision/Issue	Date
A	ISSUED FOR APPROVAL	10/07/03
D	ISSUED FOR CONSTRUCTION	10/07/03

APN: N/A
 6:\01_ProJ_Current\03-117\Draw\Rev_0\0-6.dwg 9-29-03 11:51:08 AM Tadj

HALF SIZE SET