

**REVISED PROPOSAL
TREASURE ISLAND MAIN REPLACEMENTS
CWO 03-117**



Bid Date: October 28, 2003 @ 2:00 PM

SOQUEL CREEK WATER DISTRICT

All of the proposal items below shall include all labor, materials, tools, equipment, and incidental costs for each item complete, in place, in accordance with the Standard Specifications and Standard Plans, and for the Project Special Provisions and Project Plans.

Item No.	Description	Quantity	Unit	Unit Cost (In Figures)	Total Amount (In Figures)
----------	-------------	----------	------	---------------------------	------------------------------

PIPE CONSTRUCTION

1	Install 6" C900 PVC Class 200 Pipeline and all related gate valves and fittings on Creek Dr. (from Glen Dr. to end), Glen Dr. (from Creek Dr. to Creek Dr.), Forest Dr. (from Spreckles Dr. to end), Claus Ct. (from Spreckles Dr. to end), Spreckles Dr. from Claus Ct. to Treasure Island Ave.), and Treasure Island Ave. (from Aptos Beach Drive to end)	2,860	LF		
2	Install 2" Permanent Blow-off Assembly	4	EA		
3	Installation of Chlorination Tap	2	EA		

WATER SERVICE INSTALLATIONS

4	Replace 1" Domestic Service	65	EA		
5	Reconnect 1" Domestic Service	3	EA		
6	Install 1" Air & Vacuum Release Valve	3	EA		
7	Reconnect 2" Combination Domestic/Fire Service	3	EA		

FIRE HYDRANT INSTALLATIONS

8	Installation of James Jones J-3740 6-inch Steamer Fire Hydrant and all appurtenances.	5	EA		
---	--	---	----	--	--

----Continued on Next Page----

**REVISED PROPOSAL
TREASURE ISLAND MAIN REPLACEMENTS
CWO 03-117**



Bid Date: October 28, 2003 @ 2:00 PM

SOQUEL CREEK WATER DISTRICT

All of the proposal items below shall include all labor, materials, tools, equipment, and incidental costs for each item complete, in place, in accordance with the Standard Specifications and Standard Plans, and for the Project Special Provisions and Project Plans.

Item No.	Description	Quantity	Unit	Unit Cost (In Figures)	Total Amount (In Figures)
----------	-------------	----------	------	------------------------	---------------------------

TIE-INS TO EXISTING WATER MAINS

9	Tie-In at Creek Dr. and Glen Dr.	1	EA		
10	Tie-In at Glen Dr. and Creek Dr.	1	EA		
11	Tie-In at Forest Dr. and Spreckles Dr.	1	EA		
12	Tie-In at Spreckles Dr. and Treasure Island Ave.	1	EA		
13	Tie-In at Treasure Island Ave. and Aptos Beach Dr.	2	EA		
14	Tie-In at Spreckles Dr. (east of Claus Ct.)	1	EA		

SLURRY SEAL REQUIREMENT

15	Application of road width Type II Slurry Seal per Cal-Trans Standard Specification 37-2.	13,650	SF		
----	--	--------	----	--	--

PROJECT TOTAL \$ _____
For Comparison Only

Submitted By: _____
Contractor

_____ Address

_____ Signature

_____ Phone Number

Number of Addendums Attached to Proposal: _____