

SERVICES:
 REPLACE 15 WITH 1" PE TUBING AND B-9 METER BOX
 RECONNECT 3 TO NEW MAIN (9457, 9647 & 9667 MONROE AVE)

INSTALL
 1- 8"x6" TEE (MJxMJxFLG)
 1- 6" GV (FLGxMJ)
 1- 8" GV (MJxMJ)
 1- 6" JONES J-3740 FIRE HYDRANT
 PER SCWD STANDARDS S-9
 & S-10. LOCATION TO BE
 DETERMINED IN FIELD BY
 DISTRICT INSPECTOR.


STA 24+80.21 2.52 RT
 INSTALL 8" 22.5' EL (MJ)

STA 23+16.38 11.98 RT
 INSTALL 8" G.V. (MJ X MJ)

INSTALL 1020 LF ± OF 8"
 C900 PVC CLASS 150 PIPE

STA 22+92.14 12.87 RT
 INSTALL 8" 22.5' EL(MJ)

STA 22+4.65 13.59 RT
 INSTALL 8" 22.5' EL(MJ)

No.	Revision/Issue	Date
A	ISSUED FOR APPROVAL	02/17/04
0	ISSUED FOR CONSTRUCTION	02/17/04
MONROE AVENUE MAIN REPLACEMENT		
APTOS, SANTA CRUZ COUNTY, CALIFORNIA APN: N/A G:\01_Proj_Current\03-120\Draw\Rev_0\0-3.dwg 2-24-04 09:01:45 AM ttdj		
SOQUEL CREEK WATER DISTRICT PO Box 158 Soquel, California 95073 Phone Number: (831) 475-8500 Fax Number: (831) 475-4291		
CWO. NO. 03-120 DATE: 10/30/02 SCALE: 1"=30' DESIGN BY: TAD DWG. NO. D-03-2113-F		
Certification:  Jeffery N. Gailey Chief Engineer Engineering Manager		
SHEET: D-3		