

**PROPOSAL
LA SELVA BEACH PHASE I
MAIN REPLACEMENTS
CWO 03-124**



**Bid Date: July 19, 2005 @ 2:00 PM
SOQUEL CREEK WATER DISTRICT**

All of the proposal items below shall include all labor, materials, tools, equipment, and incidental costs for each item complete, in place, in accordance with the Standard Specifications and Standard Plans, and for the Project Special Provisions and Project Plans.

| Item No. | Description | Qty. | Unit | Unit Cost (In Figures) | Total Amount (In Figures) |
|----------|-------------|------|------|---------------------------|------------------------------|
|----------|-------------|------|------|---------------------------|------------------------------|

PIPE CONSTRUCTION

| | | | | | |
|---|--|-------|----|--|--|
| 1 | Installation of 8-inch C900 PVC Class 200 Pipeline and all related valves and fittings on Playa Blvd. | 600 | LF | | |
| 2 | Installation of 6-inch C900 PVC Class 200 Pipeline and all related valves and fittings on Breve Ave., Arbolado Dr., Cresta Ave., Florido Ave., and Verdosos Ave. | 1,880 | LF | | |
| 3 | Installation of Chlorination Tap | 5 | EA | | |
| 4 | Installation of 2" Permanent Blow-off Assembly | 2 | EA | | |

WATER SERVICE INSTALLATIONS

| | | | | | |
|---|--|----|----|--|--|
| 5 | Replacement of 1-inch Domestic Service. | 32 | EA | | |
| 6 | Replacement of 2-inch Combination Domestic and Fire Service | 1 | EA | | |
| 7 | Tie-over of existing Domestic Service from abandoned main to existing 8-inch main. | 15 | EA | | |
| 8 | Reconnection of 2-inch Combination Domestic and Fire Service | 8 | EA | | |

FIRE HYDRANT INSTALLATIONS

| | | | | | |
|----|---|---|----|--|--|
| 9 | Installation of James Jones J-3740 6-inch Steamer Fire Hydrant and all appurtenances. | 5 | EA | | |
| 10 | Abandonment of Existing Wharfhead Fire Hydrant | 2 | EA | | |

----Continued on Next Page----

