

**PROPOSAL  
BAYVIEW DRIVE  
MAIN REPLACEMENT  
CWO 03-146**



**Bid Date: April 29, 2003 @ 2:00 PM**

**SOQUEL CREEK WATER DISTRICT**

All of the proposal items below shall include all labor, materials, tools, equipment, and incidental costs for each item complete, in place, in accordance with the Standard Specifications and Standard Plans, and for the Project Special Provisions and Project Plans.

Item No.	Description	Quantity	Unit	Unit Cost (In Figures)	Total Amount (In Figures)
----------	-------------	----------	------	---------------------------	------------------------------

**PIPE CONSTRUCTION**

1	<b>Installation of 6-inch C900 PVC Class 200 Pipeline and all related valves and fittings on Bayview Drive.</b>	2,735	LF		
2	<b>Installation of Chlorination Tap</b>	2	EA		

**WATER SERVICE INSTALLATIONS**

3	<b>Replace 1" Domestic Service</b>	62	EA		
4	<b>Reconnection of existing 2" Fire and Domestic Combination Service</b>	12	EA		

**FIRE HYDRANT INSTALLATIONS**

5	<b>Installation of James Jones J-3740 6-inch Steamer Fire Hydrant and all appurtenances.</b>	2	EA		
6	<b>Abandonment of Existing Wharfhead Fire Hydrant</b>	2	EA		

----Continued on Next Page----

**PROPOSAL  
BAYVIEW DRIVE  
MAIN REPLACEMENT  
CWO 03-146**



**Bid Date: April 29, 2003 @ 2:00 PM**

**SOQUEL CREEK WATER DISTRICT**

All of the proposal items below shall include all labor, materials, tools, equipment, and incidental costs for each item complete, in place, in accordance with the Standard Specifications and Standard Plans, and for the Project Special Provisions and Project Plans.

Item No.	Description	Quantity	Unit	Unit Cost (In Figures)	Total Amount (In Figures)
----------	-------------	----------	------	------------------------	---------------------------

**TIE-INS TO EXISTING WATER MAINS**

7	Tie-In to 4-inch AC Water Main at the Intersection of Bayview Dr. & Townsend Dr.	1	EA		
8	Tie-In to 6-inch AC Water Main at the Intersection of Bayview Dr. & Cliff Dr.	2	EA		
9	Tie-In to 6-inch PVC Water Main at the Intersection of Bayview Dr. & Granada Dr.	1	EA		
10	Tie-In to 6-inch PVC Water Main at the Intersection of Bayview Dr. & Toledo Dr.	1	EA		
11	Tie-In to 6-inch AC Water Main at the end of Bayview Dr.	1	EA		

**SLURRY SEAL REQUIREMENT**

12	Application of road width Type II Slurry Seal per Cal-Trans Standard Specification 37-2.	80,830	SF		
----	--	--------	----	--	--

**PROJECT TOTAL \$** \_\_\_\_\_  
For Comparison Only

**Submitted By:**

\_\_\_\_\_  
Contractor

\_\_\_\_\_  
Address

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Phone Number

Number of Addendums Attached to Proposal: \_\_\_\_\_