

PROPOSAL
STANCE AVENUE MAIN REPLACEMENT
CWO 04-25



Bid Date: May 10, 2005 @ 2:00 PM
SOQUEL CREEK WATER DISTRICT

All of the proposal items below shall include all labor, materials, tools, equipment, and incidental costs for each item complete, in place, in accordance with the Standard Specifications and Standard Plans, and for the Project Special Provisions and Project Plans.

Item No.	Description	Qty.	Unit	Unit Cost (In Figures)	Total Amount (In Figures)
----------	-------------	------	------	---------------------------	------------------------------

PIPE CONSTRUCTION

1	Installation of 6-inch C900 PVC Class 200 Pipeline and all related valves and fittings on Fairway Drive.	305	LF		
2	Installation of 6-inch C900 PVC Class 200 Pipeline and all related valves and fittings on Stance Avenue.	770	LF		
3	Installation of 1" Chlorination Tap.	1	EA		
4	Installation of 2" Temporary Blow-off Assembly.	1	EA		
5	Abandonment of existing valve & 2" Steel water main at 3670 Crestline Way.	1	LS		
6	Abandonment of existing 2" Steel water main on Fairway Dr.	1	LS		

WATER SERVICE INSTALLATIONS

7	Replacement of 1-inch Domestic Service.	10	EA		
8	Reconnection of customer side plumbing	3	EA		
9	Installation of 2-inch Combination Domestic and Fire Service.	2	EA		
10	Replacement of 2-inch Combination Domestic and Fire Service from abandoned main to the new main.	1	EA		

FIRE HYDRANT INSTALLATIONS

11	Installation of James Jones J-3740 6-inch Steamer Fire Hydrant and all appurtenances.	1	EA		
----	---	---	----	--	--

----Continued on Next Page----

