

BID SCHEDULE

FOR
DOLPHIN AND SUMNER MONITORING WELLS
Project No. 06-18

Bid Item	Description	Unit	Estimated Amount	Unit Cost	Extension
1-2	Project (Upfront)				
1	Permitting (Santa Cruz County)	LS	1		
2	Mobilization/Demobilization	LS	1		
3-11	Deep Well				
3	Drill 8 ¼" Borehole	LF	700		
4	Geophysical Logging	LS	1		
5	Backfill	LF	100		
6	Furnish and Install 3" SCH80 PVC Blank Casing	LF	580		
7	Furnish and Install 3" SCH80 PVC Screen	LF	20		
8	Furnish and Install 3" SCH80 PVC Cellar	EA	1		
9	Furnish and Install Gravel Pack	LF	35		
10	Furnish and Install Bentonite Seals	LF	5		
11	Furnish and Install Cement-Bentonite Grout	LF	560		
12-18	Intermediate and Shallow Wells				
12	Drill 6 ¼" Borehole	LF	700		
13	Furnish and Install 2" SCH40 PVC Blank Casing	LF	650		
14	Furnish and Install 2" SCH40 PVC Screen	LF	40		
15	Furnish and Install 2" SCH40 PVC Cellar	EA	2		
16	Furnish and Install Gravel Pack	LF	70		
17	Furnish and Install Bentonite Seals	LF	10		
18	Furnish and Install Cement-Bentonite Grout	LF	620		
19-21	All 3 Wells				
19	Furnish and Install Traffic Boxes and Seals	EA	3		
20	Standby Time (provide unit cost)	Hrs	0		\$ 0
21	Well Development	Hrs	24		
22-24	Project (Closeout)				
22	Drilling Fluid/Cuttings/Discharge Water Disposal	LS	1		
23	Site Cleanup/ Wellhead Completion	LS	1		

24	Submittals	LS	1		
	TOTAL BASE BID				

Total Base Bid Amount in Words: _____

ADDENDA

FOR

DOLPHIN AND SUMNER MONITORING WELLS

Project No. 06-18

The Bidder has examined all addenda (if any) during the bid period and acknowledges receipt of the following:

ADDENDUM NO. _____ DATE RECEIVED: _____

ADDENDUM NO. _____ DATE RECEIVED: _____

ADDENDUM NO. _____ DATE RECEIVED: _____

ADDENDUM NO. _____ DATE RECEIVED: _____

ADDENDUM NO. _____ DATE RECEIVED: _____