



5180 SOQUEL DR.  
PO BOX 158  
SOQUEL, CA 95073  
TEL 831-475-8500  
FAX 831-475-4291

BOARD OF DIRECTORS

BRUCE DANIELS  
President  
Dr. THOMAS LAHUE  
Vice President

DANIEL F. KRIEGE  
Dr. DON HOERNSCHEMEYER  
Dr. BRUCE JAFFE

To: **Plan Holder**

Attn.: **Bidder**

Date: **May 25, 2007**

Project: **Tank Seismic Retrofit Phase II**

CWO No.: **06-20**

**Addendum No. 2**

---

The contract documents for the **Tank Seismic Retrofit Phase II** project have been changed as follows:

- The diameter of storm drain pipe was incorrectly stated on the proposal sheet as 15". The correct diameter is 18" ADS (non-smooth wall).
- Storm drain backfill may be native material as long as it is free of organics and rocks larger than 1/4".
- Storm drain repair clamps shall have a concrete collar poured around each joint.
- Contractor shall restore dirt swale and landscaping after work is complete.
- Access to private residence shall be maintained during storm drain repair.
- Scope of work for line item 8, "Catch Basin Repair" shall consist of replacing catch basin in kind and restoring concrete surround.

**BID DATE REMAINS: Tuesday, May 29, 2007 AT 2:00 PM**

Please adjust bids accordingly. If you would like a hard copy of this addendum, you may pick one up at the District Office, 5180 Soquel Drive, Soquel, CA 95073.

Bidder acknowledges receipt of this addendum, which shall be attached to and made a part of the proposal.

---

Contractor Representative

Date

---

Soquel Creek Water District  
Jeffery N. Gailey, PE  
Engineering Manager/ Chief Engineer