

EXISTING SAMPLE STATION

IF NECESSARY:
RE-TAP MAIN, INSTALL CORP. STOP
AND RECONNECT SAMPLE STATION.
RESET VALVE AND RISER IF NEEDED.

IN-LINE 8" GATE VALVE AS PER SCWD
STD. DWG. S-6

INSTALL:
2-8" TRANSITION COUPLINGS
2-8" STUBS PVC CL 200 PIPE
1-8" MJ GV W/ MEGALUGS
1-CHRISTY G5 VALVE BOX AND LID
1-4' RISER PIPE 8" SDR 35 PVC

ABANDON EXISTING WHARFHEAD FIRE HYDRANT, CUTTING
OUT VALVE & TEE AS PER SCWD SECTION 206.08.04.

HYDRANT #3
CONNECT TO 4-INCH AC MAIN PER SCWD STD. DWG. S-7,
S-9 & S-10


INSTALL:
2-4" TRANSITION COUPLINGS
2-4" STUBS PVC CL 200 PIPE
1-4" MJ X FLG TEE
1-4" FLG GV
1-4"x6" FLG REDUCER
1-6" FLG X MJ ADAPTER
1-CHRISTY G5 VALVE BOX AND LID
1-4' RISER PIPE 8" SDR 35 PVC
1-6" PVC CL 200 PIPE (LENGTH AS REQ'D)
1-6" MJ HYDRANT BURY
1-6" JONES J-3740 FIRE HYDRANT
1-PCC THRUST BLOCK
CONCRETE AS NEEDED FOR 3'X3' PAD AND CURB REPAIR

RETAINING WALL REQ'D - REFER TO SCWD SECTION
307.05.05

ABANDON 4 EXISTING WHARFHEAD FIRE HYDRANTS, CUTTING
OUT VALVE & TEE AS PER SCWD SECTION 206.08.04.

HYDRANT #1, 2, 4 & 5
CONNECT TO 6-INCH AC MAIN PER SCWD STD. DWG. S-7,
S-9 & S-10

INSTALL:
2-6" TRANSITION COUPLINGS
2-6" STUBS PVC CL 200 PIPE
1-6" MJ X FLG TEE
1-6" MJ X FLG GV
1-CHRISTY G5 VALVE BOX AND LID
1-4' RISER PIPE 8" SDR 35 PVC
1-6" PVC CL 200 PIPE (LENGTH AS REQ'D)
1-6" MJ HYDRANT BURY
1-6" JONES J-3740 FIRE HYDRANT
1-PCC THRUST BLOCK
CONCRETE AS NEEDED FOR 3'X3' PAD AND CURB REPAIR



**FIRE HYDRANT UPGRADES AT GREENBRIER,
TAMARACK, AND PEBBLE BEACH DRIVES, AND
VALVE INSERTION IN PINEHURST DRIVE**

No.	Revision/Issue	Date
4	ISSUED FOR REVIEW	09/24/07
0	ISSUED FOR CONSTRUCTION	10/02/07


APTOS, SANTA CRUZ COUNTY, CALIFORNIA
APN: N/A
G:\01_Proj_Current\06-29\Draw\Rev_A\B-2.dwg 10-02-07 02:34:10 PM coralc

SOQUEL CREEK WATER DISTRICT
PO Box 158 Soquel, California 95073
Phone Number: (831) 475-8500
Fax Number: (831) 475-4291

REVIEWED BY: _____ O.E.M. _____ DATE _____

CWO. NO. 06-29
09/24/07
SCALE: 1:200
DESIGN BY: CCC

SHEET
B-2
DWC. NO. B-06-2157-H



Jeffery N. Gailey
Chief Engineer
Engineering Manager