

**PROPOSAL
WIXON AVE./BAYVIEW CT.
MAIN REPLACEMENT
CWO 07-154**



**Bid Date: 8/7/07 @ 2:00 PM
SOQUEL CREEK WATER DISTRICT**

All of the proposal items below shall include all labor, materials, tools, equipment, and incidental costs for each item complete, in place, in accordance with the Standard Specifications and Standard Plans, and for the Project Special Provisions and Project Plans.

Item No.	Description	Qty.	Unit	Unit Cost (In Figures)	Total Amount (In Figures)
----------	-------------	------	------	------------------------	---------------------------

PIPE CONSTRUCTION

1	Installation of 6" water main in Wixon Avenue and Bayview Court	1,230	LF		
2	Installation of 8" water main in Aptos Beach Drive	50	LF		
3	Installation of Chlorination Tap	2	EA		
4	Installation of 2" Permanent Blow-off Assembly	2	EA		

WATER SERVICE INSTALLATIONS

5	Replacement of 1-inch Domestic Service.	34	EA		
6	Reconnection of 2-inch Combination Domestic and Fire Service	2	EA		
7	Reconnection of 2-inch Fire Service	2	EA		
8	Installation of Domestic Pressure Regulating Valve on customer side of water meter.	28	EA		

FIRE HYDRANT INSTALLATIONS

9	Installation of James Jones J-3740 6-inch Steamer Fire Hydrant, w/6" lateral and Gate Valve.	3	EA		
---	--	---	----	--	--

---Continued on Next Page---

**PROPOSAL
WIXON AVE./BAYVIEW CT.
MAIN REPLACEMENT
CWO 07-154**



**Bid Date: 8/7/07 @ 2:00 PM
SOQUEL CREEK WATER DISTRICT**

All of the proposal items below shall include all labor, materials, tools, equipment, and incidental costs for each item complete, in place, in accordance with the Standard Specifications and Standard Plans, and for the Project Special Provisions and Project Plans.

Item No.	Description	Qty.	Unit	Unit Cost (In Figures)	Total Amount (In Figures)
----------	-------------	------	------	------------------------	---------------------------

TIE-INS TO AND ABANDONMENT OF EXISTING WATER MAINS

10	Tie-in existing 6" PVC main on Wixon Avenue	1	LS		
11	Tie-in existing 8" main and 4" main on Aptos Beach Drive	1	LS		
12	4" Hot-tap at Bayview Court / Spreckles Drive and Aptos Beach Drive	1	LS		
13	Abandon existing 2" Wixon Avenue Water Main between Shore View Drive PRV and 4" Gate Valve on Aptos Beach Drive	1	LS		
14	Abandon existing 2" Bayview Court Water Main to Aptos Beach Drive	1	LS		

SLURRY SEAL REQUIREMENT

15	Type II Slurry Seal per Cal-Trans Standard Specifications, Section 37-2. on Wixon Avenue	23,400	SF		
16	Type II Slurry Seal per Cal-Trans Standard Specifications, Section 37-2. on Bayview Court	9,600	SF		

PROJECT TOTAL \$ _____
For Comparison Only

Submitted By: _____
Contractor

_____ Address

_____ Signature

_____ Phone Number

Number of Addendums Attached to Proposal: _____