

**PROPOSAL
SHOREVIEW DR./VENETIAN RD.
MAIN REPLACEMENT
CWO 08-02**



**Bid Date: 10/9/07 @ 2:00 PM
SOQUEL CREEK WATER DISTRICT**

All of the proposal items below shall include all labor, materials, tools, equipment, and incidental costs for each item complete, in place, in accordance with the Standard Specifications and Standard Plans, and for the Project Special Provisions and Project Plans.

Item No.	Description	Qty.	Unit	Unit Cost (In Figures)	Total Amount (In Figures)
----------	-------------	------	------	------------------------	---------------------------

PIPE CONSTRUCTION

1	Installation of 6" water main in Shoreview Dr.	1,380	LF		
2	Installation of 6" water main in Venetian Rd.	415	LF		
3	Installation of 4" service manifold	20	LF		
4	Installation of Chlorination Tap	3	EA		
5	Installation of 2" Permanent Blow-off Assembly	3	EA		

WATER SERVICE INSTALLATIONS

6	Replacement of 1-inch Domestic Service.	41	EA		
7	Reconnection of 2-inch Combination Domestic and Fire Service	3	EA		

FIRE HYDRANT INSTALLATIONS

8	Reconnection of existing 6-inch steamer Fire Hydrant w/6" lateral and Gate Valve.	1	EA		
9	Installation of James Jones J-3740 6-inch Steamer Fire Hydrant, w/6" lateral and Gate Valve.	2	EA		

---Continued on Next Page---

**PROPOSAL
SHOREVIEW DR./VENETIAN RD.
MAIN REPLACEMENT
CWO 08-02**



**Bid Date: 10/9/07 @ 2:00 PM
SOQUEL CREEK WATER DISTRICT**

All of the proposal items below shall include all labor, materials, tools, equipment, and incidental costs for each item complete, in place, in accordance with the Standard Specifications and Standard Plans, and for the Project Special Provisions and Project Plans.

Item No.	Description	Qty.	Unit	Unit Cost (In Figures)	Total Amount (In Figures)
----------	-------------	------	------	------------------------	---------------------------

TIE-INS TO AND ABANDONMENT OF EXISTING WATER MAINS

10	Tie-in existing 8" AC main at Shoreview Dr. and Aptos Beach Dr.	1	LS		
11	8" X 6" Hot-tap at Venetian Rd. and Aptos Beach Dr.	1	LS		
12	6" Hot-tap at Marina Ave.	1	LS		
13	Abandon existing 4" & 2" Shoreview Dr. Water Main from Aptos Beach Dr. to ends	1	LS		
14	Abandon existing 2" & 1" Venetian Rd. Water Main from Aptos Beach Drive to end	1	LS		

SLURRY SEAL REQUIREMENT

15	Type III Slurry Seal per Cal-Trans Standard Specifications, Section 37-2. on Shoreview Dr.	36,125	SF		
16	Type III Slurry Seal per Cal-Trans Standard Specifications, Section 37-2. on Venetian Rd., from Aptos Beach Dr. to Marina Ave.	14,800	SF		

PROJECT TOTAL \$ _____
For Comparison Only

Submitted By: _____
Contractor

Address

Signature

Phone Number

Number of Addendums Attached to Proposal: _____