

**PROPOSAL**  
**SEACLIFF AREA MAIN REPLACEMENT PHASE II**  
**CWO 08-042**



**Bid Date: November 12, 2008 @ 2:00 PM**  
**SOQUEL CREEK WATER DISTRICT**

All of the proposal items below shall include all labor, materials, tools, equipment, and incidental costs for each item complete, in place, in accordance with the Standard Specifications and Standard Plans, and for the Project Special Provisions and Project Plans.

Item No.	Description	Qty.	Unit	Unit Cost (In Figures)	Total Amount (In Figures)
----------	-------------	------	------	------------------------	---------------------------

**PIPE CONSTRUCTION**

1	Installation of 16" Class 200 PVC and Class 350 Ductile Iron Water Main with 16" Valves and Fittings on Searidge Dr., State Park Dr., and Center Ave.	825	LF		
2	Installation of Steel Casing Pipe at Railroad Undercrossing	82	LF		
3	Installation of 16" Carrier Pipe at Railroad Undercrossing	94	LF		
4	Boring and Receiving Pits for Railroad Undercrossing	1	L.S.		
5	Installation of 12" Class 200 PVC water main with 12" Valves and Fittings on Center Ave.	1,395	LF		
6	Installation of 14" Class 200 PVC water main with 14" Valves and Fittings on Seacliff Dr.	1,100	LF		
7	Installation of 12" Class 200 PVC Water Main with 12" Valves and Fittings on Spreckles Dr. with 12" Water Main Extension	819	LF		
8	Installation of 6" Class 200 PVC Water Main with 6" Valves and Fittings on East St. between Center Ave. and North Ave., with Main Extension at Center Ave. and East St.	216	LF		
9	Installation of 8" Class 200 PVC Water Main Extension on Hillcrest Ave. and 335 Spreckles Dr.	19	LF		
10	Installation of 6" Class 200 PVC Water Main Extensions on East St. and Sea Terrace Way	33	LF		
11	Installation of 6" In-line Gate Valve on Searidge Dr.	1	EA		
12	Installation of 8" In-line Gate Valve on North Ave.	1	EA		
13	Installation of 8" In-line Gate Valve on Spreckles Dr.	1	EA		
14	Installation of 1" SCWD Air Release Valve assembly	1	EA		
15	Abandonment of Existing Water Mains and Valves.	1	L.S.		

**PROPOSAL**  
**SEACLIFF AREA MAIN REPLACEMENT PHASE II**  
**CWO 08-042**



**Bid Date: November 12, 2008 @ 2:00 PM**  
**SOQUEL CREEK WATER DISTRICT**

All of the proposal items below shall include all labor, materials, tools, equipment, and incidental costs for each item complete, in place, in accordance with the Standard Specifications and Standard Plans, and for the Project Special Provisions and Project Plans.

Item No.	Description	Qty.	Unit	Unit Cost (In Figures)	Total Amount (In Figures)
----------	-------------	------	------	------------------------	---------------------------

**WATER SERVICE INSTALLATIONS**

16	Replacement of Single Domestic Water Service	32	EA		
17	Relocation of Single Domestic Water Service to Existing Water Main at 163 and 165 East Street.	2	EA		
18	Tie-over Reconnection of Single Domestic Water Service at Spreckles Dr.	2	EA		
19	Reconnection of 2" Domestic and Fire Service with 2" Gate Valve	2	EA		
20	Reconnection of 4" Fire Service	1	EA		

**FIRE HYDRANT INSTALLATIONS**

21	Installation of James Jones J-3740 6-inch Steamer Fire Hydrant with Lateral and all Appurtenances, and Removal of Existing Wharfhead Hydrants and Appurtenances	2	EA		
22	Reconnection of 6-inch Steamer Fire Hydrant with Lateral and all Appurtenances	2	EA		

**TIE-INS TO EXISTING WATER MAINS**

23	Tie-in to Existing 6" and 12" Water Main at McGregor Dr. and Searidge Dr.	1	EA		
24	Tie-in to Existing 8" Water Main at Hillcrest Dr	1	EA		
25	Tie-in to Existing 8" Water Main at Seaclyff Dr. and State Park Dr.	1	EA		
26	Tie-in to Existing 16" Water Main at Butterfly Valve on Center Ave.	1	EA		
27	Tie-in to Existing 12" Water Main at Butterfly Valve on Center Ave. at Broadway and El Camino Del Mar	3	EA		
28	Tie-in to Existing 6" Water Main at Center Ave. and East St.	1	EA		
29	Tie-in to Existing 8" Water Main at North Ave.	1	EA		

**PROPOSAL**  
**SEACLIFF AREA MAIN REPLACEMENT PHASE II**  
**CWO 08-042**



**Bid Date: November 12, 2008 @ 2:00 PM**  
**SOQUEL CREEK WATER DISTRICT**

All of the proposal items below shall include all labor, materials, tools, equipment, and incidental costs for each item complete, in place, in accordance with the Standard Specifications and Standard Plans, and for the Project Special Provisions and Project Plans.

Item No.	Description	Qty.	Unit	Unit Cost (In Figures)	Total Amount (In Figures)
	and East St.				
30	Tie-in to Existing 6" Water Main at Center Ave. and Santa Clara Ave.	1	EA		
31	8" Hot Tap to Existing 8" Water Main at North Ave. and Seacliff Dr.	1	EA		
32	Tie-in to Existing 4" Water Main at Sea Terrace Way and Seacliff Dr.	1	EA		
33	8" Hot Tap to Existing 8" Water Main at Spreckles Dr. near Seacliff Dr.	1	EA		
34	Tie-in to Existing 12" Tee at Spreckles Dr. near Soquel Dr.	1	EA		

**SLURRY SEAL REQUIREMENT**

35	Type II Slurry Seal per Cal-Trans Standard Specifications, Section 37-2.	86,020	SF		
----	--	--------	----	--	--

**PROJECT TOTAL \$** \_\_\_\_\_  
For Comparison Only

**Submitted By:** \_\_\_\_\_  
Contractor

\_\_\_\_\_ Address

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Phone Number

Number of Addendums Attached to Proposal: \_\_\_\_\_