

**PROPOSAL**  
**SEACLIFF AREA MAIN REPLACEMENT PROJECT**  
**CWO 08-06**



**Bid Date: April 29, 2008 @ 2:00 PM**  
**SOQUEL CREEK WATER DISTRICT**

All of the proposal items below shall include all labor, materials, tools, equipment, and incidental costs for each item complete, in place, in accordance with the Standard Specifications and Standard Plans, and for the Project Special Provisions and Project Plans.

Item No.	Description	Qty.	Unit	Unit Cost (In Figures)	Total Amount (In Figures)
----------	-------------	------	------	------------------------	---------------------------

**PIPE CONSTRUCTION**

1	Installation of 8" Class 200 PVC water main w/8" Valves and Fittings on Seacliff Dr. and Broadway	3,740	LF		
2	Installation of 16" Class 200 PVC water main on Center Ave. at Broadway w/ two 16" x 8" Tees	35	LF		
3	Installation of 16" Butterfly Valve w/16" Stub and Cap w/Extra 2' Excavation at Center Ave. and Broadway	1	L.S.		
4	Installation of 12" Butterfly Valve w/16" x 12" reducer, 12" Stub and Cap w/Extra 2' Excavation at Center Ave. and Broadway	1	L.S.		
5	Installation of 6" Class 200 PVC water main w/6" Valves and Fittings on El Camino Del Mar, Kelp Lane, and all water main extensions for tie-ins.	1,360	LF		
6	Installation of two (2) 12" x 6" tees, and two (2) 12" Butterfly Valves w/Stubs and Caps w/Extra 2' Excavation @ Both Ends	1	L.S.		
7	Installation of 2" HDPE water main on Seacliff Dr. for 179, 181, & 183 Seacliff Dr.	145	LF		
8	Installation of 2" Permanent Blow-off at end of 183 Seacliff Dr., and Seacliff Dr. & El Camino Del Mar	2	EA		
9	Installation of Chlorination Tap	5	EA		

**WATER SERVICE INSTALLATIONS**

10	Replacement of Domestic/Irrigation Service w/1" P.E. Tubing	94	EA		
11	Relocate Domestic Service at 218 Seacliff Dr. w/1" P.E. Tubing	1	EA		
12	Tie over of Domestic Service w/1" P.E. Tubing from Existing Water Main	2	EA		
13	Replacement of 2" Irrigation Service w/2" Gate Valve	1	EA		
14	Reconnection of Existing 2" Fire Service w/2" Gate Valve	1	EA		
15	Reconnection of Existing 2" Fire and Domestic Combination Service w/2" Gate Valve	5	EA		

**PROPOSAL**  
**SEACLIFF AREA MAIN REPLACEMENT PROJECT**  
**CWO 08-06**



**Bid Date: April 29, 2008 @ 2:00 PM**  
**SOQUEL CREEK WATER DISTRICT**

All of the proposal items below shall include all labor, materials, tools, equipment, and incidental costs for each item complete, in place, in accordance with the Standard Specifications and Standard Plans, and for the Project Special Provisions and Project Plans.

Item No.	Description	Qty.	Unit	Unit Cost (In Figures)	Total Amount (In Figures)
----------	-------------	------	------	------------------------	---------------------------

**FIRE HYDRANT INSTALLATIONS**

16	Installation of James Jones J-3740 6-inch Steamer Fire Hydrant w/Lateral and all Appurtenances.	4	EA		
17	Reconnect Fire Hydrant at 170/172 Seacliff Dr.	1	L.S.		

**TIE-INS TO EXISTING WATER MAINS**

18	Tie-in to Existing 8" water main at Center Ave. and Broadway	1	EA		
19	Tie-in to Existing 6" water main on Broadway at Alley	1	EA		
20	Tie-in to Existing 6" water main on Santa Cruz Ave. at Seacliff Dr. and Broadway	1	EA		
21	Tie-in to Existing 6" water main on El Camino Del Mar at Seacliff Dr.	1	EA		
22	Tie-in to Existing 6" water main on San Benito Ave. at Seacliff Dr.	2	EA		
23	Tie-in to Existing 6" water main on east end of Santa Cruz Ave. at Seacliff Dr.	1	EA		
24	Tie-in to Existing 4" water main on Valencia Ave. at Seacliff Dr.	1	EA		
25	Tie-in to Existing 6" water main on Santa Clara Ave. at Seacliff Dr.	1	EA		
26	Tie-in to Existing 4" water main on Sea Terrace Way	2	EA		
27	Tie-in to Existing 6" water main on Kelp Lane	1	EA		
28	Tie-in to Existing 8" water main on Seacliff Dr. near 218 Seacliff Dr.	1	EA		
29	Hot tap tie-in at existing 6" AC main near 206 Center Ave. w/6" x 6" Tapping Sleeve and 6" Valve	1	EA		
30	Tie-in at El Camino Del Mar and Santa Clara Ave.	2	EA		
31	Tie-in at El Camino Del Mar and Valencia Ave.	2	EA		
32	Hot tap tie-in at existing 6" PVC main on El Camino Del Mar at Santa Cruz Ave. w/6" x 6"	1	EA		

**PROPOSAL**  
**SEACLIFF AREA MAIN REPLACEMENT PROJECT**  
**CWO 08-06**



**Bid Date: April 29, 2008 @ 2:00 PM**  
**SOQUEL CREEK WATER DISTRICT**

All of the proposal items below shall include all labor, materials, tools, equipment, and incidental costs for each item complete, in place, in accordance with the Standard Specifications and Standard Plans, and for the Project Special Provisions and Project Plans.

Item No.	Description	Qty.	Unit	Unit Cost (In Figures)	Total Amount (In Figures)
	Tapping Sleeve and 6" Valve				

**SLURRY SEAL REQUIREMENT**

33	Type II Slurry Seal per Cal-Trans Standard Specifications, Section 37-2.	135,640	SF		
----	--	---------	----	--	--

**PROJECT TOTAL \$** \_\_\_\_\_  
 For Comparison Only

**Submitted By:** \_\_\_\_\_  
 Contractor

\_\_\_\_\_  
 Address

\_\_\_\_\_  
 Signature

\_\_\_\_\_  
 Phone Number

Number of Addendums Attached to Proposal: \_\_\_\_\_