



5180 SOQUEL DR.
SOQUEL, CA 95073
PO BOX 1550
CAPITOLA, CA 95010
TEL 831-475-8500
FAX 831-475-4291

BOARD OF DIRECTORS

Dr. THOMAS LAHUE
President
BRUCE DANIELS
Vice President

DANIEL F. KRIEGE
Dr. DON HOERNSCHEMEYER
Dr. BRUCE JAFFE

To: **Plan Holder**

Attn.: **Bidder**

Date: **May 26, 2009**

Project: **Estates Well Treatment
Plant Recoat**

CWO No.: **09-104**

Addendum No. 1

The contract documents for the **Estates Well Treatment Plant Recoat** project have been amended as follows:

- Although the District has no information indicating the existing coating contains lead, it will be the Contractors responsibility to sample and test for lead. The Contractor shall specify a turn around time of 24 hours for the testing, and if lead based paint is found, the add alternative for lead based/hazardous material removal will be used for compensation. The attached proposal sheet has been modified to include hazardous material testing, and an add alternative for lead based/hazardous material removal. Please ensure your bid amounts are submitted on the attached sheet.
- Section 503.12, "Application" subsection M. is changed to read:

The Contractor shall provide a Dry Film Thickness (DFT) as follows:

<i>Spot Prime First coat:</i>	<i>3.0 mils minimum to 5.0 mils maximum</i>
<i>Full Prime Second coat:</i>	<i>3.0 mils minimum to 5.0 mils maximum</i>
<i>Final Urethane Finish coat:</i>	<i>2.0 mils minimum to 3.0 mils maximum</i>
<i>Minimum total DFT: 8.0 mils</i>	
<i>Maximum total DFT: 13.0 mils</i>	

BID DATE REMAINS: June 10, 2009 AT 2:00 PM

Please adjust bids accordingly. If you would like a hard copy of this addendum, you may pick one up at the District Office, 5180 Soquel Drive, Soquel, CA 95073.

Bidder acknowledges receipt of this addendum, which shall be attached to and made a part of the proposal.

Contractor Representative

Date

Soquel Creek Water District
Taj Dufour, P.E.
Operations & Maintenance Manager

PROPOSAL- REVISED 5/26/09
Estates Treatment Plant
Recoating Project
CWO 09-104



Bid Date: June 10, 2009 @ 2:00 PM

SOQUEL CREEK WATER DISTRICT

All of the proposal items below shall include all labor, materials, tools, equipment, and incidental costs for each item complete, in place, in accordance with the Standard Specifications and Standard Plans, and for the Project Special Provisions and Project Plans.

Item No.	Description	Quantity	Unit	Total Amount (In Figures)
1	Recoating Contact Vessel & Associated Piping	1	LS	
2	Recoating Filter Vessel & Associated Piping	1	LS	
3	Preparation and Recoating of Associated Above Ground Piping, handrails and Appurtenances	1	LS	
4	Painting Bollards	8	EA	
5	Sampling and Testing for Lead Based Coating with 24 hour turn around time.	1	LS	

PROJECT TOTAL

\$ _____
For Comparison Only

6	Removal and disposal of hazardous material coating. (if found during line item 5 testing)	1	LS	
---	--	---	----	--

Submitted By:

Contractor

Address

Signature

Phone Number

Number of Addendums Attached to Proposal: _____