

---

**INVITATION TO BID UPCOMING PIPELINE  
PROJECT:****VISTA DEL MAR BOOSTER STATION  
SITE IMPROVEMENTS****CWO 09-110  
APTOS, CA**

---

**PROJECT DESCRIPTION:**

The work will consist of hot tapping two existing mains on site, trenching and installing 40 L.F. of 6" PVC suction water main, and 30 L.F. of 6" PVC discharge main, 35 L.F. of above ground ductile iron pipe, core drilling the existing masonry building wall, and installing a suction and discharge piping flanged connection inside the existing building with a concrete pedestal for a future booster pump skid. Also included is the installation of one 6" flow meter and one 6" check valve. Specifications and bid documents will be available June 3, 2009 at 8am

Work is located in Aptos, CA

**ENGINEER'S ESTIMATE:     \$20,000.00****BID OPENING: June 10, 2005 @ 2 PM****BID DOCUMENTS ARE AVAILABLE FOR PURCHASE:**

**DATE:**            June 3, 2005 at 8am

**AT:**                Soquel Creek Water District  
                          Walk-In Address (Office Address):  
                          5180 Soquel Drive  
                          Soquel, CA 95073  
                          Mailing Address:  
                          P.O. Box 158  
                          Soquel, CA 95073

**COST:**            free

For more information, call the Operations Department at (831) 475-8501 ext. 127