

PROPOSAL

THE TWIN LAKES CHURCH SEAWATER INTRUSION PREVENTION PILOT RECHARGE WELL PROJECT CWO 171-504



Bid Date: December 4, 2018 @ 2:00 PM
SOQUEL CREEK WATER DISTRICT

All of the proposal items below shall include all labor, materials, tools, equipment, and incidental costs for each item complete, in place, in accordance with the Standard Specifications and Standard Plans, and the Project Special Provisions, Technical Provisions, Technical Specifications, and Project Plans.

Bid Item No.	Description	Units	Quantity	Unit Bid Price	Bid Price
1. A.	Site Clearing and Grubbing to include Tree and Root Removal, per Site Plans.	Lump Sum	1		
1. B.	Site Grading to include Temporary Driveway/Construction Entrance, per Site Plans	Lump Sum	1		
1. C.	Erosion Control, per Site Plans	Lump Sum	1		
1. D.	Temporary Above Ground Piping and Connections, per Site Plans	Lump Sum	1		
2	Mobilization and Demobilization	Lump Sum	1		
3	34-inch Surface Casing	Linear Feet	50		
4	Pilot Hole Drilling	Linear Feet	950		
5	Geophysical Logging	Lump Sum	1		
6	Cement Grout Pilot Hole	Linear Feet	130		
7	Depth-Specific Water Quality Sampling and Testing	Each	4		
8	Reaming 30-Inch Borehole	Linear Feet	180		
9	Reaming 26-Inch Borehole	Linear Feet	640		
10	Caliper Survey	Lump Sum	1		
11	16-Inch Diameter SS Blank Casing	Linear Feet	382		

Bid Item No.	Description	Units	Quantity	Unit Bid Price	Bid Price
12	16-Inch Diameter SS Well Screen	Linear Feet	470		
13	4-Inch Diameter Camera Port Pipe and Casing Entrance Box	Linear Feet	217		
14	3-inch Diameter Sounding Pipe and Casing Entry Box	Linear Feet	207		
15	2-Inch Diameter Glass Bead Feed Tube	Linear Feet	502		
16	3-Inch Diameter Glass Bead Feed Tube	Linear Feet	122		
17	Glass Bead Filter Pack	Linear Feet	740		
18	Intermediate Bentonite Seal	Linear Feet	35		
19	Grout Surface Seal	Linear Feet	90		
20	Plumbness and Alignment Testing	Lump Sum	1		
21	Air-Lift Swabbing	Hourly	47		
22	Install/Remove Test Pump with 2 ½ -Inch Diameter Access Tube	Lump Sum	1		
23	Development and Test Pumping	Hourly	80		
24	Spinner/Flow Profile Logging	Lump Sum	1		
25	Final Water Quality Testing	Lump Sum	1		
26	Install/Remove Injection Equipment	Lump Sum	1		
27	Injection Testing All Well Screens	Lump Sum	1		
28	Spinner/Injection Flow Profile Logging	Lump Sum	1		
29	Injection Testing BC (deeper) Well Screens	Lump Sum	1		
30	Injection Testing A (shallower) Well Screens	Lump Sum	1		
31	Television Well Survey	Lump Sum	1		
32	Pilot Injection Well Disinfection and Capping	Lump Sum	1		
33	Site Clean Up	Lump Sum	1		
34	Authorized Drill Rig Standby Time	Hourly	12		

Bid Item No.	Description	Units	Quantity	Unit Bid Price	Bid Price
Total Bid Price:					

Signature of Bidder _____

Title _____

Date _____

PROPOSAL IS ASSUMED TO BE VALID FOR 90 DAYS UNLESS OTHERWISE NOTED

It is understood that the foregoing quantities herein this document are approximate only and are solely for the purpose of facilitating the comparison of bids, and that the Contractor's compensation will be computed upon the basis of the actual quantities in the completed work whether they be more or less than those shown and based on the unit price.

Soquel Creek Water District reserves the right to award the Work to the lowest responsible bidder based on any single schedule or combination of schedules of bid items deemed by the District in its sole discretion, to be in the District's best interest.